BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer, Dasarahalli Division

Scheule-B

NAME OF THE WORK: Improvement to roads and drains at Kaivarnarayan swami temple surrounding area K G hally in Ward No 12 in Shettyhalli sub division

Sl. No	Description of work	Unit	Qty	Rates quoted by contractor Sri R.Shivaram	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 1.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete asper specifications.	Cum	1315.53	184.75	Rupees One Hundred Eighty Four and Seventy Five Paise Only
2	Providing and laying in position plain cement concrete cum of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	212.28	5099.17	Rupees Five Thousand Ninety Nine and Seventeen Paise Only
3	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specificaitons.	Sqm	3838.4	306.98	Rupees Three Hundred Six and Ninety Seven Paise Only
4	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications and as per directions of the Engineer-in-charge. Specification No. KBS 4.6.3- TMT bars Fe 500	Tonne	28.6	63498.20	Rupees Sixty Three Thousand Four Hundred Ninety Eight and Nineteen Paise Only

Signatureof the Contractor

Executive Engineer
Dasarahalli Division
BBMP

MANIPAL TECHNOLOGIES LIMITED, KARNATAKA
10 2014

Scanned with CamScanner

5	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mix concrete(RMC) for RCC works laid in 15 cms thick layers and well conpacted vibrating, curing, finishing with necessary cement mortar, with all lead and lifts etc., complete (exlusive of cost of steel and fabrication charges) Ready mix concrete M-20 for raft foundation, coulmn and footing, main ans secondary beams.	Cum	469.65	6159.45	Rupees Six Thousand One Hundred Fifty Nine and Forty Five Paise Only
6	Providing and laying pre-cast drain cover slab of 100mm thickness in CM1:3 including cost of all materials,labour,curing, transportation, loading, unloading etc.,as per doiirections of the Enineer-in-charge. {Data Rate sheet enclosed}	Sqm	1167.3	1851.27	Rupees One Thousand Eight Hundred Fifty One and Twenty Seven Paise Only
7	Providing and laying Pre Cast Drain Cover slabs of 250mm thickness including cost of all materials, labour, curing, transportation,loading, unloading etc.,complete as per the direction of Engineer - In- Charge. (Data Rate enclosed)	Sqm	121.5	4169.07	Rupees Four Thousand One Hundred Sixty Nine and Seven Paise Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Signatureof the Contractor

Executive Engineer
Dasarahalli Division
BBMP

Scanned with CamScanner